

N

© Origin3 Studio Ltd

THIS DRAWING IS NOT TO BE SCALED. Except for the purposes of planning applications and for legal plans where the scale bar **must** be used. Always refer to figured dimensions. Verify site dimensions prior to construction and report discrepancies immediately. This drawing is to be read in conjuction with all relevent documents and drawings.

Rev	Revision Details	Dr	Date
P19	Section references updated and private drive switch to adopted surface P76	DR	26.05.22
P18	Application Issue	DR	10.05.22
P17	Draft Application Pack Issue	NG	01.04.22
P16	Layout amendments following client meeting on 9.03.22	NG	10.03.22
P15	Layout updated following client review	NG	17.01.22
P14	Layout amended following client review and DTM	NG	20.12.21
P13	Net Area's updated. Minor layout chnages following DTM	NG	19.11.21
P12	Layout revised following design meeting and comments with client	NG	26.07.21
P11	Tier 1 housing added. Southern block structure amended for masterplan	NG	02.06.21
P10	Numbers reduced in preparation for proposed Block Plan	NG	06.05.21
P09	Block structure revised to accomodate additional units as per clients instructions	NG	23.04.21
P08	PROW alignment and internal pedestrian/cycle network amended following consultant meeting	NG	30.03.21
P07	Proposed attenuation basins replaced with swales to western boundary. Extent of existing shrubbery indicate on western edge	NG	25.03.21
P06	Layout amended to test single access option from Northern junction	NG	24.03.21
P05	Unit numbers increased and layout changes following review	NG	17.03.21
P04	Layout amendments, net area and schedule updated.	NG	15.03.21
P03	Layout revised following client comments	NG	12.03.21
P02	Site area schedule added	DR	10.02.21
P01	Initial Draft	CH	18.06.20

O3S

RIBA Chartered Practice

[redacted]

Client's Name
Edward Ware Homes Ltd & Bromford

Job Title
Snow Capel Farm

Drawing Title
Proposed Site Plan

Scale
1 : 500 @ A0
metres 10 20 30 40 50 60 70

Drawn	Checked	Date
CH	DR	09.06.20


Job No	Drawing No	Rev
3250	0030	P19

Status
PRELIMINARY

Sheet ID
3250-O3S-ZZ-XX-GA-A-0030-S0-P19

26/05/2022 14:31:14

C:\Users\davidrhodes\Documents\My Local BIM\3250-O3S-ZZ-XX-M3-A-SnowCapelFarm-Site_CENTRAL_david@origin3studio.co.uk.rvt



N

© Origin3 Studio Ltd

THIS DRAWING IS NOT TO BE SCALED . Except for the purposes of planning applications and for legal plans where the scale bar **must** be used. Always refer to figured dimensions. Verify site dimensions prior to construction and report discrepancies immediately. This drawing is to be read in conjuction with all relevent documents and drawings.

Rev	Revision Details	Dr	Date
P06	Pedestrian and Emergency visablity added to redline	DR	12.05.22
P05	Application Issue	DR	10.05.22
P04	Redline updated to include footpath along Winnycroft Lane	DR	09.05.22
P03	Draft Application Pack Issue	NG	01.04.22
P02	Redline updated to include common land edge	DR	29.03.22
P01	first issue		as sheet

O3S

[redacted]

RIBA Chartered Practices

Client's Name
Edward Ware Homes Ltd & Bromford

Job Title
Snow Capel Farm

Drawing Title
Site Location Plan

Scale
1 : 2500 @ A3

meters 25 50 75 100 125

Drawn	Checked	Date
NG	DR	17.05.21

Job No	Drawing No	Rev
3250	0001	P06

Status
PRELIMINARY

Sheet ID
3250-O3S-ZZ-XX-GA-A-0001-S0-P06

12/05/2022 12:44:05

C:\Users\davidrhodes\Documents\My Local BIM\3250-O3S-ZZ-XX-M3-A-SnowCapelFarm-Site_CENTRAL_david@origin3studio.co.uk.rvt

GREEN INFRASTRUCTURE STRATEGY PLAN

LANDSCAPE VISION

- The landscape strategy plan sets out the level of strategic spatial arrangement envisaged for the Site in order to provide a high quality landscape setting and strong green infrastructure framework to the proposed buildings. The landscape objectives of the Proposed Development include:
- Protect the Moat Schedule Monument and its setting, bringing it into long term management
- Two new arrival and departure points Winnycroft Lane on its western edge.
- Development of strategic green infrastructure to create a framework for development.
- Enhancement of Public Rights of Way, pedestrian and cycle routes through the Site.
- Enhancement of ecological corridors and boundaries throughout the Site
- Screen and buffer the M5 to the south east of the Site.
- To develop and enhance the Site boundaries as nature conservation habitats for a range of locally occurring species.

RESIDENTIAL AREAS

The residential development will incorporate areas of subtly different characters to define and create a sense of place. As a result planting will be designed to respond to the individual character areas. Semi native and ornamental hedges and ornamental shrub beds should be used in more formal areas to define the street and soften the built form. In other areas planting has the potential to be more rural in character with strategic planting used to soften the development edge and open spaces. Native species will be used adjacent to open spaces and along the Site boundaries to create an appropriate transition to the surrounding area. Appropriate street trees will be used within the residential areas to soften built form and frame local views.

A bund and buffer planting will help to reduce the noise from the M5 within residential areas and provide additional screening.

CENTRAL MOAT AND GREEN SPACE

The central open space will be imaginatively and sensitively designed to maintain the rural and special setting of the moat which as a designated Scheduled Monument will be protected and enhanced through subtle planting of native trees to give character, break up built form, whilst not impinging on the wider setting of the moat. A network of footpaths, cycle paths, opportunities for informal recreational play alongside provision of wildlife habitat will contribute to healthy lifestyles and quality of life.

BIODIVERSITY ENHANCEMENT AND GREEN LINKS

All strategic planting will incorporate species that are native and locally appropriate to the area; plant stock will be of local provenance where possible. Existing and historic field boundaries will be enhanced to reinforce and expand ecological corridors throughout the Site and to the wider Site setting where possible. These corridors will create habitat and foraging opportunities for local fauna and connect Site features.

Green links throughout the development connect areas of public space and link the development to the wider landscape.

GREEN INFRASTRUCTURE

Existing boundary hedgerows and trees will be retained (with buffers to development), reinforced and brought into regular, long-term management. This will protect visual amenity and landscape character as well as continuing to offer commuting and foraging opportunities for wildlife.

Several incidental open spaces are proposed within the development. Groups of native tree planting within the open spaces will contribute to the local amenity and biodiversity, as well as providing a green framework for the buildings in local views.

Multi-functionality is central to the green infrastructure concept and approach. It refers to the potential for green infrastructure to have a range of functions, to deliver a broad range of ecosystem services.



The Public Open Space as part of the Green Infrastructure as indicated on the proposals will be 'multifunctional', enabling the land to perform a range of functions, such as the provision for healthy recreation whilst performing services to alleviate flood risk through the use of sustainable drainage systems/ swales. These functions are not limited to recreation, but also include ecological enhancement, visual amenity improvement resulting in mental and physical health benefits for the users. Hedgerows and planting will also help to alleviate noise pollution from the M5.

Native hedges



Species rich grassland and trees to Public Open Spaces



Proposed trees



KEY TO STRATEGY PLAN

- Site contours
- Indicative proposed vehicular routes
- Pedestrian and cycle routes
- Vehicular access point
- Pedestrian/ cycle access point
- Moat- retained and brought into long term management
- Existing vegetation- retained and brought into long term management
- Proposed bund to screen and buffer the M5
- Surrounding vegetation corridors that connect to the Site
- Proposed vegetation to strengthen boundaries and contribute to a wider network of ecological corridors
- Ecological buffer planting
- Green space provision
- Existing meadow planting to be retained and brought into long term management
- Proposed trees

Existing meadow planting



Strategically placed tree/ buffer planting



Rev.	Date	Initials	Comments
C	12.05.2022	CR	Ammended to client comments
B	04.04.2022	HNG	Ammended to client comments

JBA 21/169
Green Infrastructure Strategy Plan

Client Name: Edward Ware Homes		Site Snow Capel	
Drawn by LG	Date 06/2021	Scale NTS @ A1	Rev C

James Blake Associates Ltd.
LANDSCAPE ARCHITECTURE • LANDSCAPE PLANNING • ECOLOGY • ARBORICULTURE

James Blake Associates

Snow Capel, Gloucester

H3B 973 V1
Plot 169

H3B 973 V2
Plot 168

H3B 973 V2
Plot 167

H3B 973 V1
Plot 166



StreetScene_ParkEdge_01
1 : 100

H3B 973 V2
Plot 93

H3B 1054
Plot 92

H4B 1263
Plot 91

H3B 973 V2
Plot 90



StreetScene_ParkEdge_04
1 : 100

H3B 973 V1
Plot 156

H3B 973 V2
Plot 155

H3B 973 V2
Plot 154

H3B 973 V2
Plot 153

H3B 973 V2
Plot 152

F 513 V1
Plot 148-151



StreetScene_ParkEdge_02
1 : 100

H4B 1263
Plot 107

H3B 973 V2
Plot 106

H3B 1054
Plot 105

H4B 1263
Plot 104

H3B 973 V2
Plot 103



StreetScene_ParkEdge_03
1 : 100

* To be updated with site levels

© Origin3 Studio Ltd

THIS DRAWING IS NOT TO BE SCALED
Except for the purposes of planning applications and for legal plans where the scale bar **must** be used. Always refer to figured dimensions. Verify site dimensions prior to construction and report discrepancies immediately. This drawing is to be read in conjuction with all relevent documents and drawings.

Drawn	Checked	Date
CH	DR	

Job No	Drawing No	Rev
3250	0040	P02

Status
PRELIMINARY

Sheet ID
3250-O3S-ZZ-XX-GA-A-0040-S0-P02

Drawing Title
Proposed Site Elevations - Park Edge

Scale
1 : 100 @ A0
metres 2 4 6 8 10

Client's Name
Edward Ware Homes Ltd & Bromford

Job Title
Snow Capel Farm

Rev	Revision Details	Dr	Date
P02	Application Issue	DR	10.05.22
P01	Draft Application Pack Issue	NG	01.04.22

O3S

RIBA Chartered Practice

C:\Users\davidrhodes\Documents\My Local BIM\3250-O3S-ZZ-XX-M3-A-SnowCapelFarm-Site_CENTRAL_david@origin3studio.co.uk.rvt

12/05/2022 12:48:21

H3B 973 V2 Plot 80 | **H4B 2363** Plot 79 | **H4B 2363** Plot 78 | **H3B 973 V2** Plot 77 | **H3B 973 V1** Plot 76



StreetScene_ParkEdge_05
1 : 100

H3B 973 V1 Plot 20 | **H3B 973 V1** Plot 19 | **H3B 899** Plot 18 | **H3B 899** Plot 17 | **H3B 973 V1** Plot 16



StreetScene_ParkEdge_06
1 : 100

H3B 973 V1 Plot 15 | **H3B 899** Plot 14 | **H3B 899** Plot 13 | **H3B 973 V1** Plot 12 | **H3B 973 V2** Plot 4 | **H3B 973 V2** Plot 3 | **H3B 899** Plot 2 | **H3B 973 V1** Plot 1



StreetScene_ParkEdge_07
1 : 100

* To be updated with site levels

© Origin3 Studio Ltd

THIS DRAWING IS NOT TO BE SCALED
Except for the purposes of planning applications and for legal plans where the scale bar **must** be used. Always refer to figured dimensions. Verify site dimensions prior to construction and report discrepancies immediately. This drawing is to be read in conjuction with all relevent documents and drawings.

Drawn	Checked	Date
CH	DR	

Job No	Drawing No	Rev
3250	0041	P02

Status: **PRELIMINARY**

Sheet ID: 3250-O3S-ZZ-XX-GA-A-0041-S0-P02

Drawing Title: Proposed Site Elevations - Park Edge

Scale: 1 : 100 @ A0

metres 2 4 6 8 10

Client's Name: Edward Ware Homes Ltd & Bromford

Job Title: Snow Capel Farm

Rev	Revision Details	Dr	Date
P02	Application Issue	DR	10.05.22
P01	Draft Application Pack Issue	NG	01.04.22

O3S

RIBA Chartered Practice

12/05/2022 12:50:17

C:\Users\davidrhodes\Documents\My Local BIM\3250-O3S-ZZ-XX-M3-A-SnowCapelFarm-Site_CENTRAL_david@origin3studio.co.uk.rvt

H4B 1263	**H3B 1054**	**H2B 742**	**H2B 742**	**H2B 742**	**H2B 742**	**H3B 1054**
Plot 179	Plot 181	Plot 182	Plot 183	Plot 184	Plot 185	Plot 186



StreetScene_MainStreet_01
1 : 100

H3B 973 V1	**FOG** 70 V2	**H3B 899**	**H3B 899**	**H3B 973 V1**
Plot 163	Plot 178	Plot 177	Plot 176	Plot 175



StreetScene_MainStreet_02
1 : 100

H3B 973 V2	**H2B 742**	**H2B 742**	**H2B 742**	**H2B 742**	**H2B 742**	**H2B 800**	**H3B 973 V1**	**H3B 899**	**H3B 1074**	**H3B 1074**	**H3B 1074**	**H3B 1074**
Plot 111	Plot 112	Plot 113	Plot 114	Plot 115	Plot 116	Plot 117	Plot 99	Plot 98	Plot 97	Plot 96	Plot 95	Plot 94



StreetScene_MainStreet_03
1 : 100



StreetScene_MainStreet_04
1 : 100

* To be updated with site levels

© Origin3 Studio Ltd

THIS DRAWING IS NOT TO BE SCALED
Except for the purposes of planning applications and for legal plans where the scale bar **must** be used. Always refer to figured dimensions. Verify site dimensions prior to construction and report discrepancies immediately. This drawing is to be read in conjuction with all relevent documents and drawings.

Drawn	Checked	Date
CH	DR	

Job No	Drawing No	Rev
3250	0042	P02

Status
PRELIMINARY

Sheet ID
3250-O3S-ZZ-XX-GA-A-0042-S0-P02

Drawing Title
Proposed Site Elevations - Main Street

Scale
1 : 100 @ A0
metres 2 4 6 8 10

Client's Name
Edward Ware Homes Ltd & Bromford

Job Title
Snow Capel Farm

Rev	Revision Details	Dr	Date
P02	Application Issue	DR	10.05.22
P01	Draft Application Pack Issue	NG	01.04.22

O3S

RIBA Chartered Practice

[redacted]

12/05/2022 12:53:03

C:\Users\davidrhodes\Documents\My Local BIM\3250-O3S-ZZ-XX-M3-A-SnowCapelFarm-Site_CENTRAL_david@origin3studio.co.uk.rvt

H3B 1074	H2B 742	H2B 742	H3B 973 V1	H3B 973 V3	H2B 742	H2B 742	H3B 973 V1
Plot 70	Plot 84	Plot 85	Plot 86	Plot 87	Plot 101	Plot 100	Plot 99



StreetScene_MainStreet_05
1 : 100

H3B 973 V1	H3B 899	H3B 973 V1	H3B 899	H3B 899	H3B 899	H3B 899	H3B 899	H3B 973 V1
Plot 31	Plot 30	Plot 29	Plot 28	Plot 27	Plot 26	Plot 25	Plot 24	Plot 23



StreetScene_MainStreet_06
1 : 100

H3B 899	H3B 899	H2B 742	H2B 742	H3B 1074	H3B 1074	H3B 1074	H3B 1074	H2B 742	H2B 742	H2B 742	H2B 742	H3B 973 V1
Plot 62	Plot 61	Plot 60	Plot 59	Plot 58	Plot 57	Plot 51	Plot 50	Plot 49	Plot 48	Plot 47	Plot 46	Plot 45



StreetScene_MainStreet_07
1 : 100

* To be updated with site levels

© Origin3 Studio Ltd

THIS DRAWING IS NOT TO BE SCALED
Except for the purposes of planning applications and for legal plans where the scale bar **must** be used. Always refer to figured dimensions. Verify site dimensions prior to construction and report discrepancies immediately. This drawing is to be read in conjuction with all relevent documents and drawings.

Drawn	Checked	Date
CH	DR	
Job No	Drawing No	Rev
3250	0043	P02

Status
PRELIMINARY

Sheet ID
3250-O3S-ZZ-XX-GA-A-0043-S0-P02

Drawing Title
Proposed Site Elevations - Main Street

Scale
1 : 100 @ A0
metres 2 4 6 8 10

Client's Name
Edward Ware Homes Ltd & Bromford

Job Title
Snow Capel Farm

Rev	Revision Details	Dr	Date
P02	Application Issue	DR	10.05.22
P01	Draft Application Pack Issue	NG	01.04.22

O3S

RIBA Chartered Practice

12/05/2022 12:55:55

C:\Users\davidrhodes\Documents\My Local BIM\3250-O3S-ZZ-XX-M3-A-SnowCapelFarm-Site_CENTRAL_david@origin3studio.co.uk.rvt

H3B 973 V1	H2B 742	H2B 742	H2B 742	H2B 742	H3B 899	H3B 973 V1	H3B 973 V1	H2B 742	H2B 742	H3B 973 V1
Plot 175	Plot 174	Plot 173	Plot 172	Plot 171	Plot 170	Plot 169	Plot 166	Plot 165	Plot 164	Plot 163



StreetScene_Lane_01
1 : 100



StreetScene_Lane_02
1 : 100

H4B 1072	H4B 1072	H3B 1074	H3B 1074	H3B 1074	H3B 1074	H3B 1074	WD 701 M4(3) + F 513 V1
Plot 139	Plot 138	Plot 137	Plot 136	Plot 135	Plot 134	Plot 133	Plot 127 - 132



StreetScene_Lane_03
1 : 100

H3B 973 V3	H2B 742	H2B 742	H2B 742	H2B 742	H2B 742	H2B 742	H2B 742	H3B 973 V1
Plot 118	Plot 119	Plot 120	Plot 121	Plot 122	Plot 123	Plot 124	Plot 125	Plot 126



StreetScene_Lane_04
1 : 100

* To be updated with site levels

© Origin3 Studio Ltd

THIS DRAWING IS NOT TO BE SCALED
Except for the purposes of planning applications and for legal plans where the scale bar **must** be used. Always refer to figured dimensions. Verify site dimensions prior to construction and report discrepancies immediately. This drawing is to be read in conjuction with all relevent documents and drawings.

Drawn: CH | Checked: DR | Date:
Job No: 3250 | Drawing No: 0044 | Rev: P02
Status: **PRELIMINARY**
Sheet ID: 3250-O3S-ZZ-XX-GA-A-0044-S0-P02

Drawing Title: Proposed Site Elevations - Lane

Scale: 1 : 100 @ A0
metres 2 4 6 8 10

Client's Name: Edward Ware Homes Ltd & Bromford

Job Title: Snow Capel Farm

Rev	Revision Details	Dr	Date
P02	Application Issue	DR	10.05.22
P01	Draft Application Pack Issue	NG	01.04.22

O3S

RIBA Chartered Practice

[redacted]

12/05/2022 12:58:16

C:\Users\davidrhodes\Documents\My Local BIM\3250-O3S-ZZ-XX-M3-A-SnowCapelFarm-Site_CENTRAL_david@origin3studio.co.uk.rvt

H3B 973 V1

Plot 86

H2B 742

Plot 83

H2B 742

Plot 82

H2B 742

Plot 81

H3B 973 V2

Plot 80



StreetScene_Lane_05
1 : 100

H3B 973 V1

Plot 12

H2B 742

Plot 35

H2B 742

Plot 34

H2B 742

Plot 33

H2B 742

Plot 32

H3B 973 V1

Plot 31



StreetScene_Lane_06
1 : 100

H3B 973 V1

Plot 1

H4B 1263

Plot 11

H3B 973 V1

Plot 10



StreetScene_Lane_07
1 : 100

* To be updated with site levels

© Origin3 Studio Ltd

THIS DRAWING IS NOT TO BE SCALED
Except for the purposes of planning applications and for legal plans where the scale bar **must** be used. Always refer to figured dimensions. Verify site dimensions prior to construction and report discrepancies immediately. This drawing is to be read in conjuction with all relevent documents and drawings.

Drawn	Checked	Date
CH	DR	

Job No	Drawing No	Rev
3250	0045	P02

Status
PRELIMINARY

Sheet ID
3250-O3S-ZZ-XX-GA-A-0045-S0-P02

Drawing Title
Proposed Site Elevations - Lane

Scale
1 : 100 @ A0
metres 2 4 6 8 10

Client's Name
Edward Ware Homes Ltd & Bromford

Job Title
Snow Capel Farm

Rev	Revision Details	Dr	Date
P02	Pedestrian and Emergency visability added to redline	DR	12.05.22
P01	Draft Application Pack Issue	NG	01.04.22

O3S

RIBA Chartered Practice


[redacted]

12/05/2022 13:00:36

C:\Users\davidrhodes\Documents\My Local BIM\3250-O3S-ZZ-XX-M3-A-SnowCapelFarm-Site_CENTRAL_david@origin3studio.co.uk.rvt

© Origin3 Studio Ltd

THIS DRAWING IS NOT TO BE SCALED. Except for the purposes of planning applications and for legal plans where the scale bar **must** be used. Always refer to figured dimensions. Verify site dimensions prior to construction and report discrepancies immediately. This drawing is to be read in conjuction with all relevent documents and drawings.



Adopted Street (5.5m wide carriageway, 2m footpath either side)

Adopted Lane (6-6.8m wide with localised narrowings to 4.8m in places)

Private Drives/Courts (4.1 - 4.8m wide)

Rev	Revision Details	Dr	Date
P02	Application Issue	DR	10.05.22
P01	Draft Application Pack Issue	NG	01.04.22

O3S

[redacted]

RIBA Chartered Practice

Client's Name
Edward Ware Homes Ltd & Bromford

Job Title
Snow Capel Farm

Drawing Title
Site Proposed_ Hierarchy Strategy

Scale
1 : 500 @ A0

metres 10 20 30 40 50 60 70

Drawn	Checked	Date
NG	DR	26.07.21

Job No	Drawing No	Rev
3250	0201	P02

Status
PRELIMINARY

Sheet ID
3250-O3S-ZZ-XX-GA-A-0201-S0-P02

12/05/2022 13:01:14

C:\Users\davidrhodes\Documents\My Local BIM\3250-O3S-ZZ-XX-M3-A-SnowCapelFarm-Site_CENTRAL_david@origin3studio.co.uk.rvt

© Origin3 Studio Ltd

THIS DRAWING IS NOT TO BE SCALED. Except for the purposes of planning applications and for legal plans where the scale bar **must** be used. Always refer to figured dimensions. Verify site dimensions prior to construction and report discrepancies immediately. This drawing is to be read in conjuction with all relevent documents and drawings.

Yew Trees

55.2m

PROW footpath to adjoin with approved path in Northern development (subject to approval)

Path (um)

Cycle/Pedestrian Link

Cycle/Pedestrian Link

Cycle/Pedestrian Link - with ability to be used for emergency access if required

Cycle/Pedestrian Link - with ability to be used for emergency access if required

Moat

Potential PROW diversion through POS

Drain

55.5m

WINNYCROFT LANE

Green Farm

Location suitable for electric vehicle charging point

Rev	Revision Details	Dr	Date
P03	Application Issue	DR	10.05.22
P02	Draft Application Pack Issue	NG	01.04.22
P01	first issue		as sheet

O3S

[redacted]

RIBA Chartered Practice

Client's Name

Edward Ware Homes Ltd & Bromford

Job Title

Snow Capel Farm

Drawing Title

Site Proposed_ Electric Vehicle Charging Strategy

Scale

1 : 500 @ A0

metres 10 20 30 40 50 60 70

Drawn	Checked	Date
NG	DR	26.07.21

Job No	Drawing No	Rev
3250	0203	P03

Status

PRELIMINARY

Sheet ID


3250-O3S-ZZ-XX-GA-A-0203-S0-P03

12/05/2022 13:01:50

C:\Users\davidrhodes\Documents\My Local BIM\3250-O3S-ZZ-XX-M3-A-SnowCapelFarm-Site_CENTRAL_david@origin3studio.co.uk.rvt

© Origin3 Studio Ltd

THIS DRAWING IS NOT TO BE SCALED. Except for the purposes of planning applications and for legal plans where the scale bar **must** be used. Always refer to figured dimensions. Verify site dimensions prior to construction and report discrepancies immediately. This drawing is to be read in conjuction with all relevent documents and drawings.



45m radius from appliance

20m radius reversing distance for appliance

3.7m emergency access route for appliance

Rev	Revision Details	Dr	Date
P03	Application Issue	DR	10.05.22
P02	Draft Application Pack Issue	NG	01.04.22
P01	first issue		as sheet

O3S

RIBA Chartered Practice

Client's Name
Edward Ware Homes Ltd & Bromford

Job Title
Snow Capel Farm

Drawing Title
Site Proposed_ Fire Strategy

Scale
1 : 500 @ A0

metres 10 20 30 40 50 60 70

Drawn	Checked	Date
NG	DR	26.07.21

Job No	Drawing No	Rev
3250	0205	P03

Status
PRELIMINARY

Sheet ID
3250-O3S-ZZ-XX-GA-A-0205-S0-P03

12/05/2022 13:02:08

C:\Users\davidrhodes\Documents\My Local BIM\3250-O3S-ZZ-XX-M3-A-SnowCapelFarm-Site_CENTRAL_david@origin3studio.co.uk.rvt



© Origin3 Studio Ltd

THIS DRAWING IS NOT TO BE SCALED. Except for the purposes of planning applications and for legal plans where the scale bar **must** be used. Always refer to figured dimensions. Verify site dimensions prior to construction and report discrepancies immediately. This drawing is to be read in conjuction with all relevent documents and drawings.

Cycle Store for Apartments (4 Spaces)

Private Cycle Storage for Single Dwelling (1.2 x 1.8m Shed)

Rev	Revision Details	Dr	Date
P03	Pedestrian and Emergency visablity added to redline	DR	12.05.22
P02	Draft Application Pack Issue	NG	01.04.22
P01	first issue		as sheet

O3S

[redacted]

RIBA Chartered Practice

Client's Name
Edward Ware Homes Ltd & Bromford

Job Title
Snow Capel Farm

Drawing Title
Site Proposed_Cycle Storage Strategy

Scale
As indicated @ A0

Drawn	Checked	Date
NG	DR	18.01.22

Job No	Drawing No	Rev
3250	0207	P03

Status
PRELIMINARY

Sheet ID
3250-O3S-ZZ-XX-GA-A-0207-S0-P03

12/05/2022 13:02:27

C:\Users\davidrhodes\Documents\My Local BIM\3250-O3S-ZZ-XX-M3-A-SnowCapelFarm-Site_CENTRAL_david@origin3studio.co.uk.rvt

Site - Proposed_1/500 - Cycle Storage

© Origin3 Studio Ltd

THIS DRAWING IS NOT TO BE SCALED. Except for the purposes of planning applications and for legal plans where the scale bar **must** be used. Always refer to figured dimensions. Verify site dimensions prior to construction and report discrepancies immediately. This drawing is to be read in conjuction with all relevent documents and drawings.

Social Rent

Shared Ownership

Rev	Revision Details	Dr	Date
P02	Application Issue	DR	10.05.22
P01	Draft Application Pack Issue	NG	01.04.22

[redacted]

Client's Name
Edward Ware Homes Ltd & Bromford

Job Title
Snow Capel Farm

Drawing Title
Site Proposed_S106 Housing Tenure Strategy

Scale
As indicated @ A0

Drawn	Checked	Date
NG	DR	31.03.22

Job No	Drawing No	Rev
3250	0209	P02

Status
PRELIMINARY

Sheet ID
3250-O3S-ZZ-XX-GA-A-0209-S0-P02

12/05/2022 13:02:46

C:\Users\davidrhodes\Documents\My Local BIM\3250-O3S-ZZ-XX-M3-A-SnowCapelFarm-Site_CENTRAL_david@origin3studio.co.uk.rvt

Site - Proposed_1/500 - S106 Housing Tenure Plan
1 : 500

© Origin3 Studio Ltd

THIS DRAWING IS NOT TO BE SCALED. Except for the purposes of planning applications and for legal plans where the scale bar **must** be used. Always refer to figured dimensions. Verify site dimensions prior to construction and report discrepancies immediately. This drawing is to be read in conjuction with all relevent documents and drawings.

Yew Trees

55.2m

existing overhead power line to be relocated

PROW footpath to adjoin with approved path in Northern development (subject to approval)

Path (um)

Cycle/Pedestrian Link

Cycle/Pedestrian Link - with ability to be used for emergency access if required

see landscape strategy for boundry treatment to Moat

Moat

Cycle/Pedestrian Link - with ability to be used for emergency access if required

Drain

55.5m

WINNYCROFT LANE

Green Farm

1.8m Screen Wall (Brick to match plot)

1.8m Closeboard Fence

1m Low Stone Wall

Rev	Revision Details	Dr	Date
P02	Application Issue	DR	10.05.22
P01	Draft Application Pack Issue	NG	01.04.22

O3S

[redacted]

RIBA Chartered Practice

Client's Name
Edward Ware Homes Ltd & Bromford

Job Title
Snow Capel Farm

Drawing Title
Site Proposed_Boundary Treatment Strategy

Scale
As indicated @ A0

Drawn	Checked	Date
NG	DR	31.03.22

Job No	Drawing No	Rev
3250	0210	P02

Status
PRELIMINARY

Sheet ID
3250-O3S-ZZ-XX-GA-A-0210-S0-P02

C:\Users\davidrhodes\Documents\My Local BIM\3250-O3S-ZZ-XX-M3-A-SnowCapelFarm-Site_CENTRAL_david@origin3studio.co.uk.rvt

12/05/2022 13:03:04

Site - Proposed_1/500 - Boundary Treatment Strategy
1 : 500

GENERAL NOTES:-
The Contractor is to check and verify all building and site dimensions, levels and sewer invert levels at connection points before work starts. Any discrepancy is to be reported to DDP before work commences.

The Contractor is to comply in all respects with current building legislation - Building Standard Specifications, Building Regulations etc., whether or not specifically stated on this drawing.
The drawing must be read with and checked against any structural, geotechnical or other specialist documentation provided.

This drawing is not intended to show details of foundations, ground conditions or ground contaminants. Each area of ground relied upon to support any structure depicted (including drainage) must be investigated by the Contractor. A suitable method of foundation should be provided allowing for all existing ground conditions. Any suspect or fluid ground, contaminants on or within the ground, should be further investigated by a suitable expert. Any earthwork construction shown indicates typical slopes for guidance only and should be further investigated by a suitable expert.

Where existing trees are shown to be retained they should be subject to a full Arboricultural inspection for safety.

All trees are to be planted so as to ensure they are a minimum of 5 metres from buildings. A sewer or lateral drain should not be located closer to trees/bushes/shrubs than the canopy width at mature height, except where special protection measures are provided. A tree should not be planted directly over sewers or where excavation onto the sewer or where excavation onto the sewer would require removal of the tree.

This drawing is copyright, its use or reproduction without written permission of DDP is prohibited.

All sewers which are to be the subject of a Section 104 Agreement are to be constructed in accordance with the National Water Council's Sewers for Adoption document Seventh Edition, and to the satisfaction of the adopting sewerage undertaker.

All the sewer trenches sighted within proposed roads are to be back-filled with stone, unless specific written approval is sought and received from the Local Authority's Engineer to return excavated material. Where road levels dictate, the material employed as fill is to be approved by the Local Authority's Engineer.

All adoptable pipes of 225mm diameter or less are to be E.S.V.C. Larger pipes are to be Class H concrete.
U.P.V.C. pipes may be used subject to manufacturers recommendations and specific approval of the adopting sewerage undertaker.

All lateral connections to main foul and storm sewers shall be 150Ø minimum.

All sewers are to be constructed using Class S granular bed and surround.

All sewers with less than 1.2m of cover beneath roads or 0.9m elsewhere area to have a protective cover slab.

All outfall levels and existing sewer levels are to be confirmed by the Contractor before works commence.

The existing ground levels along the route of the proposed road are to be confirmed by the Contractor before works commence.

All roads which are to be the subject of a Section 38 Agreement are to be constructed in accordance with the Local Highway Authority's current specification and to the satisfaction of the Local Highway Authority's Engineer.

All construction methods and materials employed are to be in accordance with the current road and bridgework's specification. All construction thicknesses are to be confirmed by C.B.R. test.

No responsibility will be taken for any construction work undertaken prior to receipt of technical approvals for the intended construction, or when work is not executed strictly in accordance with the drawings.

All steps to garden embankments shall be timber.

Refer to house type drawings for all down pipe positions.

All non man entry manholes to have a covers of a minimum of 450x450mm

Pedestrian Friendly MH covers to be provided where MH's are located in shared surface areas

A section 106 application to connect must be made to the water authority, the developer shall give 21 days notice prior to connection, and the works may only be undertaken by a SSIP accredited contractor.

A 150mm nominal internal diameter gravity sewer is laid to a gradient not flatter than 1:150; or a 100mm nominal internal diameter lateral drain is laid to a gradient not flatter than 1:100

A sewer or lateral drain with a nominal internal diameter of 100mm, or a lateral drain serving less than 10 properties is laid to a gradient not flatter than 1:80, where there is at least one WC connected and 1:40 if there is no WC connected.

All Storm water sewers to be 150mm Ø minimum. All Foul Water Sewers beneath adoptable highway to be 150mm Ø minimum

Key

- 20.050 — Finished Floor Level
- Proposed Retaining Walls
- Proposed external brickwork/tanking
- 57.28 — Proposed Levels
- Proposed Storm Drainage
- Proposed Foul Drainage
- Highway Gully
- S.W.F.W. I.C. Adoptable Type 3.
- S.W.F.W. I.C. Adoptable Type 4
- S.W.F.W. I.C. Private Type 3.
- S.W.F.W. I.C. Private Type 4
- Invert level to be 600mm below proposed ground level unless indicated otherwise
- S.W. rodding access. C.L. 450mm below ground level.
- S.W. yard gulley with rodding access.
- Aco surface water drain
- Air Admittance Valve to appropriate soil pipe
- Appropriate soil stack vented to external atmosphere
- Proposed 1 in 2 Banking
- Proposed steps
- Indicative Street Lighting
- Rising main

REV	BY	CHK	DESCRIPTION	DATE
B	EP	EP	Dwelling paths Indicated	12.05.2022
A	CW	TM	Engineering revised in line with revised site layout rev 16	31.03.2022

CLIENT **Bromford Homes**

PROJECT
Proposed Residential Development at Snow Capel Farm, Gloucester

STATUS **Planning**

TITLE
Engineering Layout
Sheet 1 of 3

DRG No. **3880-110-01** Rev: **B**

SCALE: **1:250** DESIGNED BY: **CW**

SIZE: **A0** DRAWN BY: **TM**

DATE: **March 2022** CHECKED BY: **EP**

DEVELOPMENT DESIGN PARTNERSHIP
PLANNING ARCHITECTURE ENGINEERING

ISSUING OFFICE:
BRIDGEND OFFICE
UNIT 2 PARC ROAD
BOCAM PARK
PENCOED
BRIDGEND
CF35 5LJ
TEL:
EMAIL:
WEBSITE:

ALSO AT:
BRISTOL OFFICE
ST JAMES COURT
CASTRIL COURT
HARBOUR ROAD
PORTISHEAD
PORTISHEAD

This drawing and the building works illustrated are copyright and may not be reproduced without written permission.

Pitches proposed a
adjacent developme

Path (um)

GENERAL NOTES:-
The Contractor is to check and verify all building and site dimensions, levels and sewer invert levels at connection points before work starts. Any discrepancy is to be reported to DDP before work commences.

The Contractor is to comply in all respects with current building legislation - Building Standard Specifications, Building Regulations etc., whether or not specifically stated on this drawing.
The drawing must be read with and checked against any structural, geotechnical or other specialist documentation provided.

This drawing is not intended to show details of foundations, ground conditions or ground contaminants. Each area of ground relied upon to support any structure depicted (including drainage) must be investigated by the Contractor. A suitable method of foundation should be provided allowing for all existing ground conditions. Any suspect or fluid ground, contaminants on or within the ground, should be further investigated by a suitable expert. Any earthwork construction shown indicates typical slopes for guidance only and should be further investigated by a suitable expert.

Where existing trees are shown to be retained they should be subject to a full Arboricultural inspection for safety.

All trees are to be planted so as to ensure they are a minimum of 5 metres from buildings. A sewer or lateral drain should not be located closer to trees/bushes/shrubs than the canopy width at mature height, except where special protection measures are provided. A tree should not be planted directly over sewers or where excavation onto the sewer or where excavation onto the sewer would require removal of the tree.

This drawing is copyright, its use or reproduction without written permission of DDP is prohibited.

All sewers which are to be the subject of a Section 104 Agreement are to be constructed in accordance with the National Water Council's Sewers for Adoption document Seventh Edition, and to the satisfaction of the adopting sewerage undertaker.

All the sewer trenches sighted within proposed roads are to be back-filled with stone, unless specific written approval is sought and received from the Local Authority's Engineer to return excavated material. Where road levels dictate, the material employed as fill is to be approved by the Local Authority's Engineer.

All adoptable pipes of 225mm diameter or less are to be E.S.V.C. Larger pipes are to be Class H concrete.
U.P.V.C. pipes may be used subject to manufacturers recommendations and specific approval of the adopting sewerage undertaker.

All lateral connections to main foul and storm sewers shall be 150Ø minimum.

All sewers are to be constructed using Class S granular bed and surround.

All sewers with less than 1.2m of cover beneath roads or 0.9m elsewhere area to have a protective cover slab.

All outfall levels and existing sewer levels are to be confirmed by the Contractor before works commence.

The existing ground levels along the route of the proposed road are to be confirmed by the Contractor before works commence.

All roads which are to be the subject of a Section 38 Agreement are to be constructed in accordance with the Local Highway Authority's current specification and to the satisfaction of the Local Highway Authority's Engineer.

All construction methods and materials employed are to be in accordance with the current road and bridgework's specification. All construction thicknesses are to be confirmed by C.B.R. test.

No responsibility will be taken for any construction work undertaken prior to receipt of technical approvals for the intended construction, or when work is not executed strictly in accordance with the drawings.

All steps to garden embankments shall be timber.

Refer to house type drawings for all down pipe positions.

All non man entry manholes to have a covers of a minimum of 450x450mm

Pedestrian Friendly MH covers to be provided where MH's are located in shared surface areas

A section 106 application to connect must be made to the water authority, the developer shall give 21 days notice prior to connection, and the works may only be undertaken by a SSIP accredited contractor.

A 150mm nominal internal diameter gravity sewer is laid to a gradient not flatter than 1:150; or a 100mm nominal internal diameter lateral drain is laid to a gradient not flatter than 1:100

A sewer or lateral drain with a nominal internal diameter of 100mm, or a lateral drain serving less than 10 properties is laid to a gradient not flatter than 1:80, where there is at least one WC connected and 1:40 if there is no WC connected.

All Storm water sewers to be 150mm Ø minimum. All Foul Water Sewers beneath adoptable highway to be 150mm Ø minimum

Key

- 20.050 Finished Floor Level
- Proposed Retaining Walls
- Proposed external brickwork/tanking
- Proposed Levels
- Proposed Storm Drainage
- Proposed Foul Drainage
- Highway Gully
- S.W./F.W. I.C. Adoptable Type 3.
- S.W./F.W. I.C. Adoptable Type 4
- S.W./F.W. I.C. Private Type 3.
- S.W./F.W. I.C. Private Type 4

Invert level to be 600mm below proposed ground level unless indicated otherwise

- S.W. rodding access. C.L. 450mm below ground level.
- S.W. yard gulley with rodding access.
- Aco surface water drain
- Air Admittance Valve to appropriate soil pipe
- Appropriate soil stack vented to external atmosphere
- Proposed 1 in 2 Banking
- Proposed steps
- Indicative Street Lighting
- Rising main

REV	BY	CHK	DESCRIPTION	DATE
B	EP	EP	Dwelling paths indicated	12.05.2022
A	CW	TM	Engineering revised in line with revised site layout rev 16	31.03.2022

CLIENT **Bromford Homes**

PROJECT
Proposed Residential Development at Snow Capel Farm, Gloucester

STATUS **Preliminary**

TITLE
Engineering Layout Sheet 2 of 3

DRG No. **3880-SK110-02** Rev: **B**

SCALE: **1:250** DESIGNED BY: **CW**

SIZE: **A1** DRAWN BY: **TM**

DATE: **May 2021** CHECKED BY: **EP**

DEVELOPMENT DESIGN PARTNERSHIP
PLANNING ARCHITECTURE ENGINEERING

ISSUING OFFICE:
BRIDGEND OFFICE
8 OLD FIELD ROAD
BOCAM PARK
PENCOED
BRIDGEND
CF35 5LJ

ALSO AT:
BRISTOL OFFICE
STUDIO 23
KESTREL COURT
HARBOUR ROAD
PORTISHED
BS20 7AN

TEL:
EMAIL:
WEBSITE:

© This drawing and the building works illustrated are copyright and may not be reproduced without written permission

Existing culvert to be upsized

Outfall into existing STW sewer at existing manhole cover subject to STW agreement

Flow Control Chamber to restrict all flows to 9.6l/s up to and including 1 in 100 year event plus climate change

Headwall into existing highway ditch subject to ordinary watercourse consent

Proposed culvert beneath access

Base levels of existing ditch to be reprofiled to provide positive gradient between culverts

Inverted siphon to avoid existing highway culvert, to be agreed with STW

Flow Control Chamber to restrict all flows to 8.7l/s up to and including 1 in 100 year event plus climate change

Existing culvert to be upsized

Cycle/Pedestrian Link

Flow Control Chamber to restrict all flows to 11.6l/s up to and including 1 in 100 year event plus climate change, chamber to include sump to remove TSS in combination with highway gullies

Headwall sited back from existing moat to allow for surface water to enter as an overland flow, area downstream of headwall constructed to allow an overland sheet flow into moat

Cycle/Pedestrian Link - with ability to be used for emergency access if required

20m³ Online Storage for 1 in 100 year event

343m³ Cellular Storage for 1 in 100 year event

Moat

Foul Water Outfall
Outfall approximately 200m north of site along Winnycroft Road

GENERAL NOTES:-
The Contractor is to check and verify all building and site dimensions, levels and sewer invert levels at connection points before work starts. Any discrepancy is to be reported to DDP before work commences.

The Contractor is to comply in all respects with current building legislation - Building Standard Specifications, Building Regulations etc., whether or not specifically stated on this drawing.
The drawing must be read with and checked against any structural, geotechnical or other specialist documentation provided.

This drawing is not intended to show details of foundations, ground conditions or ground contaminants. Each area of ground relied upon to support any structure depicted (including drainage) must be investigated by the Contractor. A suitable method of foundation should be provided allowing for all existing ground conditions. Any suspect or fluid ground, contaminants on or within the ground, should be further investigated by a suitable expert. Any earthwork construction shown indicates typical slopes for guidance only and should be further investigated by a suitable expert.

Where existing trees are shown to be retained they should be subject to a full Arboricultural inspection for safety.

All trees are to be planted so as to ensure they are a minimum of 5 metres from buildings. A sewer or lateral drain should not be located closer to trees/bushes/shrubs than the canopy width at mature height, except where special protection measures are provided. A tree should not be planted directly over sewers or where excavation onto the sewer or where excavation onto the sewer would require removal of the tree.

This drawing is copyright, its use or reproduction without written permission of DDP is prohibited.

All sewers which are to be the subject of a Section 104 Agreement are to be constructed in accordance with the National Water Council's Sewers for Adoption document Seventh Edition, and to the satisfaction of the adopting sewerage undertaker.

All the sewer trenches sighted within proposed roads are to be back-filled with stone, unless specific written approval is sought and received from the Local Authority's Engineer to return excavated material. Where road levels dictate, the material employed as fill is to be approved by the Local Authority's Engineer.

All adoptable pipes of 225mm diameter or less are to be E.S.V.C. Larger pipes are to be Class H concrete.
U.P.V.C. pipes may be used subject to manufacturers recommendations and specific approval of the adopting sewerage undertaker.

All lateral connections to main foul and storm sewers shall be 150Ø minimum.

All sewers are to be constructed using Class S granular bed and surround.

All sewers with less than 1.2m of cover beneath roads or 0.9m elsewhere area to have a protective cover slab.

All outfall levels and existing sewer levels are to be confirmed by the Contractor before works commence.

The existing ground levels along the route of the proposed road are to be confirmed by the Contractor before works commence.

All roads which are to be the subject of a Section 38 Agreement are to be constructed in accordance with the Local Highway Authority's current specification and to the satisfaction of the Local Highway Authority's Engineer.

All construction methods and materials employed are to be in accordance with the current road and bridgework's specification. All construction thicknesses are to be confirmed by C.B.R. test.

No responsibility will be taken for any construction work undertaken prior to receipt of technical approvals for the intended construction, or when work is not executed strictly in accordance with the drawings.

All steps to garden embankments shall be timber.

Refer to house type drawings for all down pipe positions.

All non man entry manholes to have a covers of a minimum of 450x450mm

Pedestrian Friendly MH covers to be provided where MH's are located in shared surface areas

A section 106 application to connect must be made to the water authority, the developer shall give 21 days notice prior to connection. and the works may only be undertaken by a SSIP accredited contractor.

A 150mm nominal internal diameter gravity sewer is laid to a gradient not flatter than 1:150; or a 100mm nominal internal diameter lateral drain is laid to a gradient not flatter than 1:100

A sewer or lateral drain with a nominal internal diameter of 100mm, or a lateral drain serving less than 10 properties is laid to a gradient not flatter than 1:80, where there is at least one WC connected and 1:40 if there is no WC connected.

All Storm water sewers to be 150mm Ø minimum. All Foul Water Sewers beneath adoptable highway to be 150mm Ø minimum

Key
- 20.050 Finished Floor Level
- Proposed Retaining Walls
- Proposed external brickwork/tanking
- 17.28 Proposed Levels
- Proposed Storm Drainage
- Proposed Foul Drainage
- Highway Gully
- S.W./F.W. I.C. Adoptable Type 3.
- S.W./F.W. I.C. Adoptable Type 4
- S.W./F.W. I.C. Private Type 3.
- S.W./F.W. I.C. Private Type 4
- Invert level to be 600mm below proposed ground level unless indicated otherwise
- S.W. rodding access. C.L. 450mm below ground level.
- S.W. yard gulley with rodding access.
- Aco surface water drain
- Air Admittance Valve to appropriate soil pipe
- Appropriate soil stack vented to external atmosphere
- Proposed 1 in 2 Banking
- Proposed steps
- Indicative Street Lighting
- Rising main

REV	BY	CHK	DESCRIPTION	DATE
C	EP	EP	S12 and S13 relocated, Dwelling paths indicated	12.05.2022
B	EP	EP	Foul outfall revised	05.04.22
A	CW	TM	Engineering revised in line with revised site layout rev 16	31.03.2022

CLIENT **Bromford Homes**


PROJECT
Proposed Residential Development at Snow Capel Farm, Gloucester

STATUS **Planning**

TITLE
Engineering Layout Sheet 3 of 3


DRG No. **3880-110-03** Rev: **C**
SCALE: **1:250** DESIGNED BY: **CW**
SIZE: **A0** DRAWN BY: **TM**
DATE: **March 2022** CHECKED BY: **EP**

DEVELOPMENT DESIGN PARTNERSHIP
PLANNING ARCHITECTURE ENGINEERING
ISSUING OFFICE: 9 OLD FIELD ROAD BOCAM PARK PENCOED CARDIFF CF35 5LJ
ALSO AT: BRISTOL OFFICE STUDIO 23 KESTREL COURT HARBOUR ROAD PORTISHEAD
TEL: [redacted]
EMAIL:
WEBSITE:
© This drawing and the building works illustrated are copyright and may not be reproduced without written permission.


ROAD 4
TH1
ROAD 2
ROAD 3
ROAD 4
ROAD 5
ROAD 6
Culvert beneath site entrance
60.000
55.000
50.000
DATUM 45.000

ROAD 1

| | | |



TH 4

| | | |

SURFACE WATER NETWORK 1
MANHOLE SCHEDULE
Sheet 1 of 2

Manhole Number / Coordinates	Cover Level / Depth To Soffit	Connections	Pipe: Code	Inverts	Dimensions (mm)	Manhole Size	Types: Manhole	Cover
S1	59.001		1	1.000	57.576	225		
E. 385081.780	1.200		0	1.000	57.576	225	1350	C	D400
N. 214011.097								
S2	59.282		1	1.000	57.275	225		
E. 385081.574	1.782		2	2.000	57.275	225		
N. 214061.298			0	1.001	57.275	225	1200	B	D400
S3	58.769		1	1.001	57.124	225		
E. 385056.322	1.420		0	1.002	57.124	225	1350	C	D400
N. 214061.909								
S4	57.960		1	1.002	56.535	225		
E. 385029.116	1.200		0	1.003	56.535	225	1350	C	D400
N. 214069.717								
S5	56.646		1	1.003	55.221	225		
E. 384995.444	1.200		0	1.004	55.146	300	1350	C	D400
N. 214079.165								
S6	56.085		1	1.004	54.883	300		
E. 384999.221	0.902		2	3.001	54.958	225		
N. 214143.516			0	1.005	54.883	300	1350	C	D400
S7	56.822		1	1.005	54.797	300		
E. 385007.573	1.725		0	1.006	54.324	2x1500	1500	Weholite	D400
N. 214162.850								
S8	56.610		1	1.006	54.210	2x1500		
E. 385012.834	1.950		0	1.007	54.210	450	1500	Weholite	D400
N. 214219.657								
S9	56.550		1	1.007	54.182	450		
E. 385013.862	1.918		0	1.008	54.182	2x1500	1500	Weholite	D400
N. 214230.750								
S10	56.550		1	1.008	54.114	2x1500		
E. 385017.018	1.836		2	4.006	54.114	600		
N. 214264.831			0	1.009	54.114	600	3000	Flow Control	D400
S11	55.920		1	1.009	54.032	600		
E. 385020.149	1.288		0	1.010	54.032	600	1500	C	D400
N. 214305.490								
S12	55.766		1	1.010	53.967	600		
E. 385030.103	1.200		2	6.001	54.041	525		
N. 214333.412			0	1.011	53.966	600	1500	C	D400
S13	55.900		1	1.011	53.945	600		
E. 385024.379	1.710		0	1.012	53.945	225	3000	Flow Control	D400
N. 214342.062								
S14	55.000		1	1.012	53.904	225		
E. 385018.200	0.871						Headwall	Headwall	Headwall
N. 214344.950								
S15	59.714							
E. 385102.719	1.200		0	2.000	58.289	225	1350	C	D400
N. 214061.583								
S16	58.343							
E. 385042.937	1.200		0	3.000	56.918	225	1350	C	D400
N. 214104.878								
S17	57.963		1	3.000	56.538	225		
E. 385042.947	1.200		0	3.001	56.538	225	1350	C	D400
N. 214140.954								
S18	58.870							
E. 385177.971	1.200		0	4.000	57.445	225	1350	C	D400
N. 214267.732								

SURFACE WATER NETWORK 1
MANHOLE SCHEDULE
Sheet 2 of 2

Manhole Number / Coordinates	Cover Level / Depth To Soffit	Connections	Pipe: Code	Inverts	Dimensions (mm)	Manhole Size	Types: Manhole	Cover
S19	58.532		1	4.000	57.107	225		
E. 385167.485	1.200		0	4.001	57.107	225	1350	C	D400
N. 214284.566								
S20	58.088		1	4.001	56.663	225		
E. 385142.237	1.200		0	4.002	56.663	225	1350	C	D400
N. 214297.828								
S21	57.462		1	4.002	56.037	225		
E. 385102.603	1.200		0	4.003	56.037	225	1350	C	D400
N. 214304.019								
S22	57.535		1	4.003	55.854	225		
E. 385096.216	1.456		0	4.004	55.779	300	1350	C	D400
N. 214274.072								
S23	57.599		1	4.004	55.669	300		
E. 385086.664	1.630		0	4.005	54.469	1500	1500	Weholite	D400
N. 214258.391								
S24	56.000		1	5.001	54.296	600		
E. 385024.829	1.104		2	4.005	54.296	1500		
N. 214264.051			0	4.006	54.296	600	1500	Weholite	D400
S25	56.500							
E. 385020.976	1.132		0	5.000	54.367	600	1350	B	D400
N. 214230.420								
S26	56.500		1	5.000	54.309	600		
E. 385024.373	1.591		0	5.001	54.309	600	1350	B	D400
N. 214259.072								
S27	56.617							
E. 385079.884	1.200		0	6.000	55.192	225	1350	C	D400
N. 214310.061								
S28	55.788		1	6.000	54.363	225		
E. 385040.588	1.200		0	6.001	54.063	525	1500	B	D400
N. 214331.483								

SURFACE WATER NETWORK 2
MANHOLE SCHEDULE
Sheet 1 of 2

Manhole Number / Coordinates	Cover Level / Depth To Soffit	Connections	Pipe: Code	Inverts	Dimensions (mm)	Manhole Size	Types: Manhole	Cover
S29	60.794		1	1.000	59.369	225		
E. 385177.226	1.200		0	1.000	59.369	225	1350	C	D400
N. 214083.161								
S30	60.646		1	1.000	59.221	225		
E. 385161.113	1.200		0	1.001	59.221	225	1350	C	D400
N. 214071.056								
S31	60.340		1	1.001	58.915	225		
E. 385135.173	1.200		0	1.002	58.915	225	1350	C	D400
N. 214064.082								
S32	60.182		1	1.002	58.757	225		
E. 385130.183	1.200		0	1.003	58.682	300	1350	C	D400
N. 214070.188								
S33	60.012		1	1.003	58.512	300		
E. 385129.916	1.200		0	1.004	58.512	300	1350	C	D400
N. 214089.467								
S34	59.926		1	1.004	58.426	300		
E. 385125.213	1.200		0	1.005	58.426	300	1350	C	D400
N. 214098.995								
S35	59.361		1	1.005	57.861	300		
E. 385105.269	1.200		0	1.006	57.861	300	1350	C	D400
N. 214120.154								
S36	59.350		1	1.006	57.777	300		
E. 385118.825	1.273		0	1.007	57.702	375	1350	C	D400
N. 214135.629								
S37	60.200		1	1.007	57.551	375		
E. 385146.173	2.274		2	2.004	58.563	225		
N. 214160.409			0	1.008	56.988	2x1800	1800	Weholite	D400
S38	60.000		1	1.008	56.896	2x1800		
E. 385159.430	1.364		2	3.003	58.336	300		
N. 214204.696			0	1.009	56.896	2x1800	1800	Weholite	D400
S39	60.000		1	1.009	56.841	2x1800		
E. 385167.292	2.072		2	4.006	57.628	300		
N. 214231.299			0	1.010	56.841	2x1800	1800	Weholite	D400
S40	59.430		1	1.010	56.730	2x1800		
E. 385117.508	2.100		0	1.011	56.730	600	1800	Weholite	D400
N. 214256.278								
S41	59.000		1	5.001	56.713	450		
E. 385111.236	2.062		2	1.011	56.713	600		
N. 214251.663			0	1.012	56.713	225	3000	Flow Control	D400
S42	57.495		1	1.012	56.610	225		
E. 385095.947	0.660						Headwall	Headwall	Headwall
N. 214243.768								
S43	61.640							
E. 385226.107	1.200		0	2.000	60.215	225	1350	C	D400
N. 214123.510								
S44	61.012		1	2.000	59.587	225		
E. 385195.403	1.200		0	2.001	59.587	225	1350	C	D400
N. 214099.950								
S45	60.760		1	2.001	59.335	225		
E. 385183.528	1.200		0	2.002	59.335	225	1350	C	D400
N. 214114.269								
S46	60.370		1	2.002	58.945	225		
E. 385164.517	1.200		0	2.003	58.945	225	1350	C	D400
N. 214136.436								

SURFACE WATER NETWORK 2
MANHOLE SCHEDULE
Sheet 2 of 2

Manhole Number / Coordinates	Cover Level / Depth To Soffit	Connections	Pipe: Code	Inverts	Dimensions (mm)	Manhole Size	Types: Manhole	Cover
S47	60.173		1	2.003	58.748	225		
E. 385149.102	1.200		0	2.004	58.748	225	1350	C	D400
N. 214155.596								
S48	61.488							
E. 385223.935	1.200		0	3.000	60.063	225	1350	C	D400
N. 214157.421								
S49	61.002		1	3.000	59.577	225		
E. 385208.203	1.200		0	3.001	59.577	225	1350	C	D400
N. 214173.346								
S50	59.921		1	3.001	58.496	225		
E. 385168.494	1.200		0	3.002	58.496	225	1350	C	D400
N. 214190.290								
S51	59.858		1	3.002	58.451	225		
E. 385168.613	1.182		0	3.003	58.376	300	1350	C	D400
N. 214201.301								
S52	61.450							
E. 385277.010	1.200		0	4.000	60.025	225	1350	C	D400
N. 214179.884								
S53	60.675		1	4.000	59.250	225		
E. 385253.877	1.200		0	4.001	59.250	225	1350	C	D400
N. 214205.355								
S54	60.328		1	4.001	58.903	225		
E. 385241.341	1.200		0	4.002	58.903	225	1350	C	D400
N. 214214.178								
S55	60.188		1	4.002	58.763	225		
E. 385227.436	1.200		0	4.003	58.763	225	1350	C	D400
N. 214216.143								
S56	59.992		1	4.003	58.567	225		
E. 385222.117	1.200		0	4.004	58.567	225	1350	C	D400
N. 214224.242								
S57	59.650		1	4.004	58.225	225		
E. 385205.555	1.200		0	4.005	58.225	225	1350	C	D400
N. 214232.774								
S58	59.245		1	4.005	57.820	225		
E. 385189.423	1.200		0	4.006	57.745	300	1350	C	D400
N. 214249.502								
S59	59.150							
E. 385161.654	1.313		0	5.000	56.836	450	1350	C	D400
N. 214226.341								
S60	59.000		1	5.000	56.733	450		
E. 385115.704	1.817		0	5.001	56.733	450	1350	B	D400
N. 214249.419								

REV	BY	CHK	DESCRIPTION	DATE
A	EP	EP	S12 and S13 relocated	12.05.22

CLIENT **Bromford Homes**

PROJECT
Proposed Residential Development at Snow Capel Farm, Gloucester

STATUS **Preliminary**

TITLE
Surface Water Manhole Schedules

DRG No. **3880-115-2** | Rev: **A**

SCALE: | DESIGNED BY: **EP**

SIZE: **A0** | DRAWN BY: **EP**

DATE: **March 2022** | CHECKED BY: **EP**


DEVELOPMENT DESIGN PARTNERSHIP
PLANNING ARCHITECTURE ENGINEERING

ISSUING OFFICE:
BRIDGEND OFFICE
UNIT 2 COITY ROAD
BOCAM PARK
PENCOED
BRIDGEND
CF35 5LJ


TEL: [redacted]
EMAIL:
WEBSITE:


ALSO AT:
BRISTOL OFFICE
ST CATHERINE'S
COURT, CASTLE
HARBOUR ROAD
PORTISHEAD
BRISTOL

© This drawing and the building works illustrated are copyright and may not be reproduced without written permission.



Cross Section through Schematic Drainage Outfall into Existing Moat





Moat Outfall arrangement (NTS)





REV	BY	CHK	DESCRIPTION	DATE
B	EP	EP	Latest engineering proposals indicated	11.05.22
A	EP	EP	Indicative Development layout included	22.09.21

CLIENT **Bromford Homes**

PROJECT
Proposed Residential Development at Snow Capel Farm, Gloucester

STATUS **Preliminary**

TITLE
Schematic Drainage into Moat

DRG No. **3880-125** Rev: **B**

SCALE: **1:500** DESIGNED BY: **EP**

SIZE: **A0** DRAWN BY: **EP**

DATE: **August 2021** CHECKED BY: **CRW**

DEVELOPMENT DESIGN PARTNERSHIP
PLANNING ARCHITECTURE ENGINEERING

ISSUING OFFICE:
BRIDGEND OFFICE
UNIT 2 PARC ERW
ROCAM PARK
PENCOED
BRIDGEND
CF35 5LJ

ALSO AT:
BRISTOL OFFICE
1ST FLOOR
CENTRAL COURT
HARBOUR ROAD
PORTISHEAD
BS20 7PG

TEL:
EMAIL:
WEBSITE:

© This drawing and the building works illustrated are copyright and may not be reproduced without written permission

Water main taken from pdf overlay

Gas Line taken from pdf overlay

Foul Outfall Route
1:250

Extract on Siphon
1:100

REV	BY	CHK	DESCRIPTION	DATE
A	EP	EP	Water and Gas main overlays added	12.05.2022

CLIENT **Bromford Homes**

PROJECT
Proposed Residential Development at Snow Capel Farm, Gloucester

STATUS **Preliminary**

TITLE
Foul Outfall Radar Overlay

DRG No. **3880-SK112** | Rev: **A**

SCALE: **As shown** | DESIGNED BY: **EP**

SIZE: **A1** | DRAWN BY: **EP**

DATE: **April 2022** | CHECKED BY: **EP**

DEVELOPMENT DESIGN PARTNERSHIP
PLANNING ARCHITECTURE ENGINEERING

ISSUING OFFICE:
BRIDGEND OFFICE
8 OLD FIELD ROAD
BOCAM PARK
PENCOED
BRIDGEND
CF35 5LJ

ALSO AT:
BRISTOL OFFICE
STUDIO 23
KESTREL COURT
HARBOUR ROAD
PORTISHED
BS20 7AN

TEL:
EMAIL:
WEBSITE:

© This drawing and the building works illustrated are copyright and may not be reproduced without written permission



LEGEND

- Outline of adoptable area; Refer to Adoption Strategy Plan.
- Site Boundary.
- Proposed trees. Locations of new trees to be >4m from lighting column. Final tree planting proposals to be reviewed to ensure distance of any tree from lighting column is maintained prior to build.
- RC Rear Cowl to be affixed to lanterns as indicated.
- Lux contours for reference only.
  - 0.60 Lux
  - 2.00 Lux
  - 4.00 Lux

ADOPTABLE LIGHTING UNIT:

CU Phosco hot dip galvanised tubular steel lighting column of **6m** lantern mounting height. Root protection and treated in accordance with GCC specification. Column door to be fitted with SL2 8mm allen bolt with anti vandal centre pin.
Columns to be factory painted. Base; dark green BS4800 12B29, shaft; light green BS4800 12B21.**TBC**
Urbis Ampera Mini - optic 5240, 8 Oslon Square LED warm white 3000k, 700mA (19.7w, 2.05klm)
Aluminium canopy, colour 7040 (grey). Lantern to be post top mounted at 0 degree tilt.
Lantern to include Philips Xitanium dimmable driver; Constant Light Output (CLO and DALI) with 7 pin NEMA socket for NEMA mounted Telensa telecell, GPS enabled. Code:T2E1N-G-3. Dimming to be set to 30% of light output between the hours of 12:00 midnight to 05:30am. (UMSUG :00 0000 0000 000).

CU Phosco hot dip galvanised tubular steel lighting column of **6m** lantern mounting height. Root protection and treated in accordance with GCC specification. Column door to be fitted with SL2 8mm allen bolt with anti vandal centre pin.
Columns to be factory painted. Base; dark green BS4800 12B29, shaft; light green BS4800 12B21.**TBC**
Urbis Ampera Mini - optic 5239, 8 Oslon Square LED warm white 3000k, 600mA (17w, 1.83klm)
Aluminium canopy, colour 7040 (grey). Lantern to be post top mounted at 0 degree tilt.
Lantern to include Philips Xitanium dimmable driver; Constant Light Output (CLO and DALI) with 7 pin NEMA socket for NEMA mounted Telensa telecell, GPS enabled. Code:T2E1N-G-3. Dimming to be set to 30% of light output between the hours of 12:00 midnight to 05:30am. (UMSUG :00 0000 0000 00).

SUPPLIES:

All ADOPTABLE columns to be fed from Distribution Network Operator LV supply networks: Western Power Distribution (WPD).
Lucy trojan double pole fused isolator to be fitted on backboard within each column above DNO cut out.
If an IDNO is proposed, then a service level agreement should be in place with GCC and notice provided to the Lighting Engineer for confirmation of acceptance prior to connection works proceeding.

The installation of lighting and electrical equipment must comply with the Manual for Gloucestershire Streets section 10 (Street Lighting Rev1), follow manufacturers guidance / instruction and be in compliance with the current edition of IEE Wiring Regulations.
GCC street lighting specification document is available and MUST be referred to in conjunction with this drawing and during scheme equipment purchase and installation.

Telensa CMS and lighting scheme dimming to be confirmed by GCC.
Should the lanterns need to be powered and controlled before CMS connection is available, or in place of telecells, on/off control may be achieved via a 7 pin NEMA mounted one part Photo Electric Control Unit (Selc or similar) set to 35 Lux on and 18 Lux off.

LIGHTING SCHEME NOTES:

1. Any alterations to the positions of columns and associated illuminated equipment to that as shown on this drawing must be referred to the designer to ensure compliance with lighting level requirements before installation. Re-submission to Gloucestershire County Council for further technical approval may be required. Any installation without GCC approval will be at risk.
2. Setting out should be conducted by a competent person and notice provided to GCC via Highways Development Manager (HDM) in good time to arrange a site visit where required.
3. All column doors to face away from on coming traffic unless access restricted or otherwise specified. Ensure correct orientation of lanterns (lens direction) as detailed within drawing.
4. New column numbering as detailed is for reference only. Developer to request numbering schedule and fixing detail from Development Management prior to application for completion certificate.
5. In order to avoid future maintenance issues and ensure efficiency of lighting scheme, planting of trees and shrubbery in vicinity of street lighting equipment is to be avoided. Tree plans should be reviewed following agreed column locations to provide a recommended minimum distance of 4m from tree to column.
6. Columns are to be planted to the rear of footways within adopted land only. Columns should not be located within shared surface but within a 1mx1m build out linked to the adoptable road. Such build outs should be included within the adoptable agreement plan (refer to standard Detail: appendix G/02).
7. Columns planted in soft verge to have a concrete collar and be located to a minimum of 1m clearance from back of kerb, or to rear of service strip. For foundation detail refer to GCC Standard Detail;J11.
8. Agreed column locations should be included within sales plans to inform prospective house buyers of lighting column locations prior to their purchase.
9. Where Telensa telecell's are installed, detail / unit reference code to be recorded within base of column for ease of CMS configuration. In addition to Telecell's, a base station may be required as part of the installation if there is no capacity with existing CMS equipment. For CMS details and equipment specification to GCC standard contact Telensa on Tel: 01799 533257.

DESIGN METHODOLOGY AND NOTES:

A Proposed lighting scheme complies to BS5489-1 2020 lighting class:
P5 for all adoptable roads (Eav=3.00 to 4.50 Emin=0.60). No SP ratio applied.

B Public lighting by column mounted luminaires is not proposed for the small private areas. Bulk head style lanterns will be mounted onto each property frontage to illuminate property entrance. Such lighting will be energy efficient, low wattage, soft white light LED type. Type and mounting of bulk head will be considered to ensure illumination is adequate for property frontage without excessive light spill beyond property boundary, minimum glare and zero upward light spill.

C To minimise light spill onto the moat area, public lighting for the adoptable multi use paths is not proposed. In addition, rear cowls will be mounted onto lanterns in vicinity of moat to further control light spill and to keep the areas as dark as possible.

D With reference to Ecology assessment, there is potential for bat activity along boundaries. Generally low level of illumination along roads with use of warm white 3000K LED's. Low light spill into boundary areas , zero degree post top lantern mounting, to minimise glare and provide zero upward light spill. Inclusion of rear cowls as an additional light reduction measure is an option to be discussed with the Ecologist. Bat and bird boxes to be mounted within site should be located in co-ordination of lighting columns to minimise roosting / nesting disturbance.

23/04/22	Draft 1	Removed two columns. Issued to Client for comment.
01/04/22	Draft 1	Issued to Client for comment / Planning submission.

PURPOSE OF ISSUE
FOR COMMENT ONLY

DRAWING IN PROGRESS
NOT FOR CONSTRUCTION

Lighting scheme proposals for adoption must be technically approved by adopting Authority before works commence. Any works prior to final technical approval may be conducted "at risk".

HEALTH AND SAFETY NOTE: UNDERGROUND & OVERHEAD SERVICES IN VICINITY OF WORKS.

This design has been completed with limited information pertaining to underground and overhead services. Full service details should be sought and consulted prior to the commencement of street lighting works. Works in the vicinity of underground and over-ground utilities must be in accordance with current HSE guidance notes including HSG47, HSG6 and NJUG guidelines.
Contractor advised to use suitable underground services locator in conjunction with services drawings prior to commencement of excavation works. To hand dig existing surfaces for column root foundations to avoid contact and damage to underground services in vicinity of works.
Avoid high lifting equipment and manually plant columns in vicinity of overhead cables.

HIGHWAY LIGHTING SOLUTIONS Ltd
55, Gorsefield Avenue
Bromborough, Wirral, CH62 6BY
[redacted]

Project:
Bromford Developments Ltd
S38 Road Lighting

Location:
Snow Capel Farm
Winneycroft Lane

Drawn by:	Ken Duckers	**Date:**	30/03/22
Checked by:	Ian Buckley	**Date:**	
Telephone:	0151 327 2424	**Fax:**	0151 327 2424
Scale @ A0: 1:500	**Drawing No.:** HLS-846	**Sheet:** 1 of 1	**Revision:** Draft 2

Masterplan



HERITAGE INTERPRETATION BOARD

PROPOSED LANDSCAPE AREAS








TREE PALETTE

Native Focal Trees such as Acer campestre, Betula pendula and Carpinus betulus.



Betula pendula

Street Trees such as Acer campestre "Streetwise" and Carpinus betulus "Frans Fontaine"



Acer campestre "Streetwise"

Ornamental Trees such as Pyrus calleryana "Chanticleer" and Prunus "Amanogawa"



Pyrus calleryana "Chanticleer"

KEY TO MASTERPLAN

Soft Landscape

- Existing Vegetation
- Proposed Ornamental Shrub Planting
- Proposed Ground Cover Planting
- Proposed Ornamental Hedge Planting
- Proposed Native Buffer Planting
- Proposed Native Hedge Planting
- Amenity Grass to Public Open Space Areas
- Back Garden Grass
- Plot Frontage Grass
- Mown Path
- Wildflower Meadow Grassland
- Proposed Planted Acoustic Bund
- Area of Retained Vegetation

Hard Landscape

- Tarmac Paths
- Proposed Road and Parking Space Tarmac Surfacing
- Proposed Block Paving to Shared Surfaces and Private Drives
- Timber Post and Split Rail Fencing
- Slab Paving
- 3m High Accoustic Fence

Streetscape Items

- Picnic Table
- Heritage Interpretation Board
- Finger Post
- Naturalistic Play Items

Rev.	Date	Initials	Comments
B	13.05.2022	CR	Ammended to client comments
A	10.05.2022	CR	Ammended to client comments

Site
Snow Capel, Matson, Gloucester

Drg Number
JBA 21/169- SK01

Client
Edward Ware Homes

Drawn by	Date	Scale	Rev
HNG	APRIL 2022	1:1000@A1	B

[redacted]

JAMES BLAKE ASSOCIATES

Snow Capel, Matson, Gloucester

N

Yew Trees

Pitches proposed as part of adjacent development

Existing stile location

Path (um)

Moat

Dam

55.5m

PENNYCROFT LANE

Key:

- Site Boundary
- Proposed 3m Footway/Cycleway & Part Diversion of Footpath EUL24
- Proposed 1m Buffer
- Approximate Alignment of Existing PRoW EUL23
- Approximate Alignment of Existing PRoW EUL23 to be stopped up as part of the development proposals
- Approximate Alignment of Existing PRoW EUL24
- Approximate Alignment of Existing PRoW EUL24 to be diverted as part of the development proposals
- Potential Continuation of Footway/ Cycleway (exact location to be determined)
- Approximate Alignment of Existing EUL24 to be retained
- Approximate Alignment of PRoW EUL23 diversion understood to be coming forward as part ofBarratt Scheme
- Approximate Alignment of Trodden Route



Image 1: Picture showing trodden route, as observed during site visit undertaken 27.01.22



Image 2: Picture showing existing style from south from the proposed site, as observed during site visit undertaken 27.01.22

First Floor, South Wing, Equinox North Great Park Road, Almondsbury, Bristol , BS32 4QL

[redacted]

www.pegasusgroup.co.uk

Planning | Design | Environment | Economics

Pegasus Group

REV	DATE	BY	DESCRIPTION	CHK	APD

CLIENT: BROMFORD DEVELOPMENTS LTD	SCALE @ A0: 1:500	CHECKED: KSS	APPROVED: CMR
PROJECT: LAND AT SNOW CAPEL	DATE: 31/05/2022	DESIGN/DRAWN: JAN	DRAWING STATUS: FOR INFO
TITLE: PROPOSED PUBLIC RIGHT OF WAY DIVERSION AND EXTINGUISHMENT	PROJECT No: P20-1432	DRAWING No: SK/11	REV: -

Copyright Pegasus Planning Group Ltd. Crown copyright. All rights reserved. Ordnance Survey Copyright Licence number 100042093. Promap Licence number 100020449. Emapsite Licence number 0100031673. Standard OS licence rights conditions apply. Pegasus accepts no liability for any use of this document other than for its original purpose, or by the original client, or following Pegasus' express agreement to such use. T 01285 641717 www.pegasusgroup.co.uk

G:\BROS\PROJECTS\P20-1432 - LAND AT SNOW CAPEL, METHERINGHAM\PLANNING\DRAWINGS\SK\SK11 - LAND AT SNOW CAPEL METHERINGHAM (PROPOSED PUBLIC RIGHT OF WAY DIVERSION AND EXTINGUISHMENT).DWG | PRIOR | 31/05/2022 | JAN